

F/G 13/13

DACW43-78-C-0160

1 of 1

AD A  
105986

END  
DATE  
FILMED  
11-81  
DTIC

MISSISSIPPI - SALT - QUINCY RIVER BASIN

AD A105888

MISSOURI POWER AND LIGHT DAM

AUDRAIN COUNTY, MISSOURI

MO 10065

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

Missouri Power and Light Dam (MO 10065),  
Mississippi - Salt - Quincy River Basin,  
Audrain County, Missouri. Phase I Inspection  
Report.

DTIC FILE COPY



Final rept.

15 DACW43-78-C-0160

DTIC  
ELECTE  
S OCT 21 1981

A

PREPARED BY: U. S. ARMY ENGINEER DISTRICT, ST. LOUIS

FOR: STATE OF MISSOURI

This document has been approved  
for public release and sale; its  
distribution is unlimited.

DEC 1978

10 10 19

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO. AD-A105888	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Dam Inspection Report National Dam Safety Program Missouri Power and Light Dam (MO 10065) Audrain County, Missouri		5. TYPE OF REPORT & PERIOD COVERED Final Report
7. AUTHOR(s) Consoer, Townsend and Associates, Ltd.		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		8. CONTRACT OR GRANT NUMBER(s) DACW43-78-C-0160
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE December 1978
		13. NUMBER OF PAGES Approximately 70
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report)  Approved for release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number)  Dam Safety, Lake, Dam Inspection, Private Dams		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report was prepared under the National Program of Inspection of Non-Federal Dams. This report assesses the general condition of the dam with respect to safety, based on available data and on visual inspection, to determine if the dam poses hazards to human life or property.		

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

## INSTRUCTIONS FOR PREPARATION OF REPORT DOCUMENTATION PAGE

**RESPONSIBILITY.** The controlling DoD office will be responsible for completion of the Report Documentation Page, DD Form 1473, in all technical reports prepared by or for DoD organizations.

**CLASSIFICATION.** Since this Report Documentation Page, DD Form 1473, is used in preparing announcements, bibliographies, and data banks, it should be unclassified if possible. If a classification is required, identify the classified items on the page by the appropriate symbol.

### COMPLETION GUIDE

**General.** Make Blocks 1, 4, 5, 6, 7, 11, 13, 15, and 16 agree with the corresponding information on the report cover. Leave Blocks 2 and 3 blank.

**Block 1.** Report Number. Enter the unique alphanumeric report number shown on the cover.

**Block 2.** Government Accession No. Leave Blank. This space is for use by the Defense Documentation Center.

**Block 3.** Recipient's Catalog Number. Leave blank. This space is for the use of the report recipient to assist in future retrieval of the document.

**Block 4.** Title and Subtitle. Enter the title in all capital letters exactly as it appears on the publication. Titles should be unclassified whenever possible. Write out the English equivalent for Greek letters and mathematical symbols in the title (see "Abstracting Scientific and Technical Reports of Defense-sponsored RDT&E," AD-667 000). If the report has a subtitle, this subtitle should follow the main title, be separated by a comma or semicolon if appropriate, and be initially capitalized. If a publication has a title in a foreign language, translate the title into English and follow the English translation with the title in the original language. Make every effort to simplify the title before publication.

**Block 5.** Type of Report and Period Covered. Indicate here whether report is interim, final, etc., and, if applicable, inclusive dates of period covered, such as the life of a contract covered in a final contractor report.

**Block 6.** Performing Organization Report Number. Only numbers other than the official report number shown in Block 1, such as series numbers for in-house reports or a contractor/grantee number assigned by him, will be placed in this space. If no such numbers are used, leave this space blank.

**Block 7.** Author(s). Include corresponding information from the report cover. Give the name(s) of the author(s) in conventional order (for example, John R. Doe or, if author prefers, J. Robert Doe). In addition, list the affiliation of an author if it differs from that of the performing organization.

**Block 8.** Contract or Grant Number(s). For a contractor or grantee report, enter the complete contract or grant number(s) under which the work reported was accomplished. Leave blank in in-house reports.

**Block 9.** Performing Organization Name and Address. For in-house reports enter the name and address, including office symbol, of the performing activity. For contractor or grantee reports enter the name and address of the contractor or grantee who prepared the report and identify the appropriate corporate division, school, laboratory, etc., of the author. List city, state, and ZIP Code.

**Block 10.** Program Element, Project, Task Area, and Work Unit Numbers. Enter here the number code from the applicable Department of Defense form, such as the DD Form 1498, "Research and Technology Work Unit Summary" or the DD Form 1634, "Research and Development Planning Summary," which identifies the program element, project, task area, and work unit or equivalent under which the work was authorized.

**Block 11.** Controlling Office Name and Address. Enter the full, official name and address, including office symbol, of the controlling office. (Equates to funding/sponsoring agency. For definition see DoD Directive 5200.20, "Distribution Statements on Technical Documents.")

**Block 12.** Report Date. Enter here the day, month, and year or month and year as shown on the cover.

**Block 13.** Number of Pages. Enter the total number of pages.

**Block 14.** Monitoring Agency Name and Address (if different from Controlling Office). For use when the controlling or funding office does not directly administer a project, contract, or grant, but delegates the administrative responsibility to another organization.

**Blocks 15 & 15a.** Security Classification of the Report: Declassification/Downgrading Schedule of the Report. Enter in 15 the highest classification of the report. If appropriate, enter in 15a the declassification/downgrading schedule of the report, using the abbreviations for declassification/downgrading schedules listed in paragraph 4-207 of DoD 5200.1-R.

**Block 16.** Distribution Statement of the Report. Insert here the applicable distribution statement of the report from DoD Directive 5200.20, "Distribution Statements on Technical Documents."

**Block 17.** Distribution Statement (of the abstract entered in Block 20, if different from the distribution statement of the report). Insert here the applicable distribution statement of the abstract from DoD Directive 5200.20, "Distribution Statements on Technical Documents."

**Block 18.** Supplementary Notes. Enter information not included elsewhere but useful, such as: Prepared in cooperation with . . . Translation of (or by) . . . Presented at conference of . . . To be published in . . .

**Block 19.** Key Words. Select terms or short phrases that identify the principal subjects covered in the report, and are sufficiently specific and precise to be used as index entries for cataloging, conforming to standard terminology. The DoD "Thesaurus of Engineering and Scientific Terms" (TEST), AD-672 000, can be helpful.

**Block 20.** Abstract. The abstract should be a brief (not to exceed 200 words) factual summary of the most significant information contained in the report. If possible, the abstract of a classified report should be unclassified and the abstract to an unclassified report should consist of publicly-releasable information. If the report contains a significant bibliography or literature survey, mention it here. For information on preparing abstracts see "Abstracting Scientific and Technical Reports of Defense-Sponsored RDT&E," AD-667 000.



DEPARTMENT OF THE ARMY  
ST. LOUIS DISTRICT, CORPS OF ENGINEERS  
210 NORTH 12TH STREET  
ST. LOUIS, MISSOURI 63101

IN REPLY REFER TO

SUBJECT: Missouri Power and Light Dam (Mo. 10065),  
Phase I Inspection Report

This report presents the results of field inspection and evaluation of Missouri Power and Light Dam (Mo. 10065).

The St. Louis District has classified this dam as unsafe, emergency, requiring immediate attention because of heavy brush and tree growth on the downstream embankment slope, the excessively steep and sloughing downstream embankment slope, seepage on the downstream embankment slope and at the toe of the dam, and a seriously inadequate spillway which will pass only 17 percent of the Probable Maximum Flood.

SUBMITTED BY:

SIGNED

Chief, Engineering Division

5 JAN 1979

(Date)

APPROVED BY:

SIGNED

Colonel, CE, District Engineer

8 JAN 1979

(Date)

Accession For	
FEIS GRA&I	<input checked="checked" type="checkbox"/>
ERIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A	

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

Name of Dam: Missouri Power and Light Dam, Inv. No. 10065  
State Located: Missouri  
County Located: Audrain  
Stream: Unnamed Tributary of North Fork of Salt River  
Date of Inspection: September 29 and 30, 1978

Missouri Power and Light Dam No. Mo.10065 was inspected using the "Recommended Guidelines for Safety Inspection of Dams". These guidelines were developed by the Chief of Engineers, U.S. Army, Washington, D.C., with the help of Federal and state agencies, professional engineering organizations, and private engineers. The resulting guidelines are considered to represent a consensus of the engineering profession.

Based on the criteria in the guidelines, the dam is in the high hazard potential classification, which means that loss of life and appreciable property loss could occur in the event of failure of the dam. Four houses, one church and related buildings, three County roads, and one U.S. highway would be subjected to flooding, with possible damage and/or destruction, and possible loss of life. Missouri Power and Light Dam is in the small size classification since it is less than 40 feet high and impounds less than 1,000 acre-feet of water.

Our inspection and evaluation indicates that the spillway of Missouri Power and Light Dam does not meet the criteria set forth in the guidelines for a dam having the above size and hazard potential. Missouri Power and Light Dam is a small size dam with a high hazard potential required by the guidelines to pass from one-half Probable Maximum Flood to the Probable Maximum Flood without overtopping. Since there is significant hazard potential downstream of the dam, the appropriate spillway design flood for this dam is a flood somewhat greater than one-half of the Probable Maximum Flood. It was determined that the spillway will pass 17 percent of the Probable Maximum Flood without overtopping the dam. Our evaluation indicates that the spillway will pass the 100-year flood; that is, a flood having a 1 percent chance of being equalled or exceeded during any given year.

The Probable Maximum Flood is defined as the flood discharge that may be expected from the most severe combination of critical meteorological and hydrologic conditions that are reasonably possible in the region.

Other deficiencies noted by the inspection team were the questionable stability of a recently repaired section of the embankment; large trees and brush on the downstream embankment slope; an unstable upstream embankment slope; extensive rodent activity on the embankment; deteriorated concrete in the spillway structure; obstructions in the downstream discharge channel; a need for an annual inspection by a qualified engineer; and lack of a maintenance schedule. The lack of stability and seepage analysis on record is also a deficiency that should be corrected.

It is recommended that the owner take action to correct or control the deficiencies described above.



MISSOURI POWER AND LIGHT CO.



PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

Missouri Power and Light Dam, I.D. No. 10065

TABLE OF CONTENTS

<u>Sect. No.</u>	<u>Title</u>	<u>Page</u>
SECTION 1	PROJECT INFORMATION . . . . .	1
	1.1 General . . . . .	1
	1.2 Description of Project . . . . .	3
	1.3 Pertinent Data . . . . .	7
SECTION 2	ENGINEERING DATA . . . . .	9
	2.1 Design . . . . .	9
	2.2 Construction . . . . .	9
	2.3 Operation . . . . .	9
	2.4 Evaluation . . . . .	10
SECTION 3	VISUAL INSPECTION . . . . .	12
	3.1 Findings . . . . .	12
	3.2 Evaluation . . . . .	15
SECTION 4	OPERATION PROECEDURES . . . . .	17
	4.1 Procedures . . . . .	17
	4.2 Maintenance of Dam . . . . .	17
	4.3 Maintenance of Operating Facilities . . . . .	17
	4.4 Description of Any Warning System in Effect . . . . .	18
	4.5 Evaluation . . . . .	18
SECTION 5	HYDRAULIC/HYDROLOGIC . . . . .	19
	5.1 Evaluation of Features . . . . .	19

TABLE OF CONTENTS  
(Continued)

<u>Sect. No.</u>	<u>Title</u>	<u>Page</u>
SECTION 6	STRUCTURAL STABILITY . . . . .	23
	6.1 Evaluation of Structural Stability . . . . .	23
SECTION 7	ASSESSMENT/REMEDIAL MEASURES . . . . .	25
	7.1 Dam Assessment . . . . .	25
	7.2 Remedial Measures . . . . .	28

LIST OF PLATES

	<u>Plate No.</u>
LOCATION MAP . . . . .	1
PLAN AND ELEVATION OF DAM . . . . .	2
GENERAL GEOLOGIC MAP . . . . .	3

APPENDICES

APPENDIX A	-	PHOTOGRAPHS TAKEN DURING INSPECTION
APPENDIX B	-	HYDROLOGIC COMPUTATIONS

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

MISSOURI POWER AND LIGHT DAM, Missouri Inv. No. 10065

SECTION 1: PROJECT INFORMATION

1.1 General

a. Authority

The Dam Inspection Act, Public Law 92-367 of August, 1972, authorizes the Secretary of the Army, through the Corps of Engineers, to initiate a national program of dam inspections. Inspection for the Missouri Power and Light Dam was carried out under Contract DACW 43-78-C-0160 to the Department of the Army, St. Louis District, Corps of Engineers, by the engineering firms of Consoer, Townsend & Associated Ltd., and Engineering Consultants, Inc. (A Joint Venture), of St. Louis, Missouri.

b. Purpose of Inspection

The visual inspection of the Missouri Power and Light Dam was made on September 29, and September 30, 1978. The purpose of the inspection was to make a general assessment as to the structural integrity and operational adequacy of the dam embankment and its appurtenant structures.

c. Scope of Report

This report summarizes available pertinent data relating to the project; presents a summary of visual observations made during the field inspection; presents an evaluation of hydrologic and hydraulic conditions at the site; presents an evaluation as to the structural adequacy of the various project features; and assesses the general condition of the dam with respect to safety.

It should be noted that reference in this report to left or right abutments is as viewed looking downstream. Where left abutment or left side of the dam is used in this report, this also refers to north abutment or side, and right to the south abutment or side.

d. Evaluation Criteria

Criteria used to evaluate the dam were furnished by the Department of the Army, Office of the Chief of Engineers, in "Recommended Guidelines for Safety Inspection of Dams", Appendix D. These guidelines were developed with the help of Federal agencies and many state agencies, professional engineering organizations, and private engineers".

## 1.2 Description of the Project

### a. Description of Dam and Appurtenances

The dam embankment is a homogeneous earthfill structure. The crest of the dam typically has a width of 14-feet, and a length of approximately 637 feet. The crest elevation is set at 795.67 feet above MSL, and the maximum height of the embankment is approximately 26 feet above the minimum streambed elevation.

The upstream slope of the embankment is vertical for the top 4 feet. This vertical section of embankment is protected by a wall constructed of loose blocks of used concrete and rocks. These blocks are typically 6-inches high by 2-feet thick. Below the top 4 feet, the embankment has an unprotected slope of approximately 1V to 3H to the base of the dam.

The downstream embankment slope is protected by heavy vegetation, and has a typical slope of 1V to 1-1/2 to 2H. This slope is very uneven and irregular.

No information is available regarding the embankment material. Field inspection demonstrated the material to be low plastic clay with traces of silt and sand. The material would be classified as CL by the Unified Soil Classification System.

Bedrock within the vicinity is composed of cyclic deposits, including limestones of Pennsylvanian age. The soils of the area in which this dam is located are considered to be mixed glacial outwash, modified with loessial deposits, further modified by weathering. No bedrock crops out over the

site, and data is not available to describe the foundation conditions or preparation previous to placement of the embankment.

The uncontrolled concrete spillway is located on the left abutment of the embankment near the Lake View Road. The spillway consists of a concrete broad crested weir section, a concrete drop section with five steps, and a concrete apron at the end of the drop structure before entering the downstream channel. The spillway crest length is 46 feet, and the broad crest width is 6 feet. The drop section has five steps; each step drops 3 feet, except the last step which drops only 2 feet. Total length from the crest to the spillway floor apron is 21 feet, 4 inches. The apron length is 22 feet. A cross-section of the spillway is given in a plate in this report.

Except for the spillway, there is no gravity flow outlet from the reservoir. A pump station adjacent to the reservoir provides the only permanent means for drawing down the reservoir. The station contains one small pump (approximately 4-inch discharge), which is occasionally operated to supply make-up water to the cooling tower of a nearby steam-electric plant. The pump suction draws water from a supply sump constructed on the bank of the reservoir. The sump is concrete, about 12 feet in diameter, and fitted with a heavy wooden cover. The cover contains a hinged inspection door which is padlocked for security.

A representative of the owner reported that the supply sump is connected to the reservoir through one or two intake pipes which extend into the reservoir.

The reservoir for Missouri Power and Light Dam impounds 224 acre-feet of water from a drainage area of 1.20 square miles. The reservoir is located in an urban area of Mexico, Missouri, surrounded by roads and two parks.

b. Location

The Missouri Power and Light Dam is located on an unnamed tributary of the North Fork of the Salt River, Audrain County, Missouri. The nearest community downstream of the dam is Mexico, Missouri. A church and associated buildings are located immediately downstream of the dam. The dam and reservoir is shown on Mexico West Quadrangle sheet (7.5 minute series) in Section 35, Township 51 North, Range 9 West.

c. Size Classification

According to the "Recommended Guidelines for Safety Inspection of Dams", by the U.S. Department of the Army, Office of the Chief Engineer, the dam is classified in the dam size category as being "Small" since its storage is less than 1,000 acre-feet. The dam is also classified as "Small" in dam size category because its height is less than 40 feet. The overall size classification is, accordingly, "Small" in size.

d. Hazard Classification

The dam has been classified as having "High" hazard potential in the National Inventory of Dams, on the basis that in the event of failure of the dam or its appurtenances, excessive damage could occur to downstream property, together with the possibility of the loss of life. Our findings concur with the classification. The estimated damage zone extends two miles downstream of the dam. Within the damage zone are

four houses, one church and related buildings, three county roads, and one U.S. highway.

e. Ownership

Missouri Power and Light Dam is owned by the Missouri Power and Light Company, 101 Madison Street, Jefferson City, Missouri 65101.

f. Purpose of Dam

The main purpose of the dam is to impound water for use in a cooling water system for power plants operated by the Missouri Power and Light Company. The reservoir is also used for recreational purposes.

g. Design and Construction History

Design and construction history of the dam is very incomplete. According to the owner, the dam was designed and built prior to 1910, possibly as early as 1885. In 1911, the original spillway washed out and was replaced with the present structure.

Recent work at the dam has included repair of a leak through the embankment section in July, 1978.

h. Normal Operational Procedures

The dam is used to impound water for use as cooling water for a power plant, and for recreation. The reservoir level is controlled by rainfall, runoff, evaporation, and the water supply requirements of the power plant. The reservoir remains close to full at all times.



### 1.3

### Pertinent Data

a. Drainage Area

769 acres

b. Discharge at Damsite

All discharge at the dam-site is through an uncontrolled spillway

Estimated experienced maximum flood:

340 cfs

Estimated ungated spillway capacity  
at maximum pool elevation:

867 cfs

c. Elevation (Feet above MSL)

Top of dam:

795.67

Spillway crest:

792.0

Minimum streambed elevation at centerline of dam:

769.0

Maximum tailwater:

Unknown

d. Reservoir

Length of maximum pool:

2,700 feet +

e. Storage (Acre-Feet)

Top of dam:

330

f. Reservoir Surface (Acres)

Top of dam:

30

Spillway crest:

28

g. Dam

**Type:**

Earth embankment

**Length:**

637 feet

Height (maximum):

26 feet

Top width:

**Varies - 14 feet typical**

Side slopes:

Downstream	1V to 1-1/2 to 2H
Upstream	Vertical for top 4 feet, 1V to 3H for remainder of slope to ground surface

Zoning:	Unknown
---------	---------

Impervious core:	Unknown
------------------	---------

Cutoff:	Unknown
---------	---------

Grout curtain:	Unknown
----------------	---------

h. Diversion and Regulating Tunnel	None
------------------------------------	------

i. Spillway

Type:	Uncontrolled
Length of weir:	46 feet
Crest Elevation:	792 feet (MSL)

j. Regulating Outlets	None
-----------------------	------

A pump station adjacent to the reservoir can draw water from the reservoir.

## SECTION 2: ENGINEERING DATA

### 2.1 Design

No design data is available for the dam and appurtenant structures. A plate was made for this report, based upon visual observations and measurements made during the field inspection.

### 2.2 Construction

The only construction data available is a Missouri Public Service Commission inventory which provides some basic information concerning the dam. In this inventory, the dam is described as "earthfill constructed of Dry earth borrow from reservoir site put in place by teams". A representative of the owner indicated that construction was "sometime before 1910, and probably about 1885."

Reconstruction of the dam included replacement of the original spillway which was washed out during a flood in 1911. Also, a section of embankment exhibiting a leak was repaired in July, 1978.

### 2.3 Operation

No operation records for Missouri Power and Light Dam are available.

## 2.4 Evaluation

### a. Availability

Essentially, no information is available for the dam and appurtenant structures. The inventory data on the dam is the only available information.

No pertinent data was available for review of hydrology, spillway capacity, flood routing through the reservoir, outlet capacity, slope stability, seepage analysis, or foundation conditions.

### b. Adequacy

The engineering data available is inadequate to aid in evaluating the hydraulic and hydrologic capabilities and stability of the dam for Phase I investigations. The owner should have a survey performed and an as-built set of drawings made for the dam and appurtenant structures.

The lack of engineering data, other than design drawings, did not allow for a definitive review and evaluation. Therefore, the adequacy of this dam could not be assessed from the standpoint of reviewing and evaluating design and construction, but is based primarily on visual inspection with the aid of the available design drawings, past performance history, and sound engineering judgment.

Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency. These seepage and stability analyses should be performed for appropriate loading conditions (including earthquake loads) and made a matter of record.

c. Validity

The only available information, the dam inventory listing, is of questionable validity since it was likely made well after the original construction.

### SECTION 3: VISUAL INSPECTION

#### 3.1 Findings

##### a. General

A visual inspection of Missouri Power and Light Dam was made on September 29, and September 30, 1978. The following persons were present during the inspection:

<u>Name</u>	<u>Affiliation</u>	<u>Discipline</u>
Yin Au-Yeung	Engineering Consultants, Inc.	Project Engineer, Hydraulics and Hydrology
David Bramwell	Engineering Consultants, Inc.	Geology
Jon Diebel	Engineering Consultants, Inc.	Soils & Stability
John Ismert	Engineering Consultants, Inc.	Mechanical
Kevin Blume	Consoer, Townsend & Assoc., Ltd.	Civil & Structural

Specific observations are discussed below.

##### b. Dam

The crest of the dam is adequately protected by a heavy vegetative cover. The upstream slope of the embankment is in deteriorated condition. The wall constructed of loose blocks of used concrete and rocks is unstable in many places, appearing to be on the verge of failing into the reservoir. Cracking, indicating movement, can be seen behind the wall in several areas. Extensive rodent activity is occurring on the upstream slope and crest. Several large holes could be seen which are likely occupied by muskrats. Shells of fresh water

clams could be seen along the upstream slope of the embankment, confirming the presence of muskrats.

The downstream slope of the embankment is also in deteriorated condition. Heavy brush and tree growth is present on the slope. The heavy vegetation made it difficult to inspect the embankment slope, but several areas were moist and contained vegetation indicating potential seepage. The slope itself is very steep, and sloughing was prevalent. The slope is generally uneven and irregular.

One section of the embankment has been recently repaired, located approximately 125 feet from the right abutment. A leak had developed on the downstream embankment slope, and attempts to repair the leak by addition of material to the upstream embankment slope proved unsuccessful. The reservoir was then lowered several feet, and a section of embankment 4-feet wide by 8 to 10-feet deep was excavated. The excavated section was then replaced with a mixture of nearby clay and "fireclay". A representative of the owner indicated that compaction was achieved with the bucket of the backhoe, and visual inspection did not reveal the compaction to be satisfactory.

In the foundation materials adjacent to the toe of the downstream embankment slope, ponds of water, phreatophytes, and desiccation cracks, trending normal to the dam axis, were prevalent. These observations were seen mostly on either side of the former channel section. Telephone poles were observed downstream of the toe of the dam on the upstream slope of the embankment, and in close proximity to the spillway discharge channel.

c. Appurtenant Structures

(1) Spillway

The concrete in the spillway structure is in deteriorated condition. Heavy vegetative growth was noted on the left side of the approach channel. Erosion, spalling, and cracks in concrete were noted in the structure. The downstream channel is obstructed by fallen tree trunks and debris, and the channel banks show signs of erosion and sloughing.

(2) Pumping Plant

The interior of the pumping station and the pump were inspected. The station is also used as a storage building. The station is clean and, considering its age, in reasonably good condition. Since the pump is used only intermittently, the station is normally unattended and locked. The most recent operation of the pump was in the spring of 1978. The supply sump was inspected; its water surface was clean. The intake pipes were not observed since they are under water.

d. Reservoir Area

The water level was at elevation 790.58 feet above MSL at the time of the inspection.

There have been no apparent changes in the drainage basin that would affect the runoff characteristics, or the stability of the reservoir rim, since the dam was constructed. The watershed is in an urbanized area, and the reservoir shoreline is a City Park which is very well maintained.



e. Downstream Channel

The downstream channel has not been adequately maintained. Tree trunks and debris were observed within 200 feet downstream of the spillway. The downstream channel has been moderately eroded during past floods. Signs of sloughing were noted on the bank slopes. The channel cross-section immediately downstream from the spillway is trapezoidal in shape, with a bottom width of 10 feet, and side slopes of 1V to 2H. The channel runs along the parking lot of the Luthern Church, and through a 8' x 13'-4" culvert under U.S. Highway 54.

3.2 Evaluation

A large number of observations were made at Missouri Power and Light Dam which could affect the safety of the dam, and which will require remedial measures, monitoring, or maintenance in the near future. These items include:

1. The deteriorated condition of the upstream embankment slope.
2. The extensive rodent activity occurring in the embankment section.
3. The heavy brush and tree growth on the downstream embankment slope.
4. The steep and sloughing downstream embankment slope, which includes a poorly repaired section of embankment.

5. The seepage observed downstream of the toe of the embankment demonstrated by ponds, phreatophytes, and desiccation cracks.
6. The deteriorated condition of the concrete spillway.
7. The condition of the downstream channel of the spillway, which contains tree trunks and other obstructions. Also, erosion and sloughing is occurring on the channel banks.

## SECTION 4: OPERATIONAL PROCEDURES

### 4.1 Procedures

Missouri Power and Light Dam is used to impound water from an unnamed tributary of the North Fork of the Salt River. The water is used for cooling water for a power plant, and the reservoir is also used for recreation. The only operating facility at the damsite is the pump station adjacent to the reservoir. Water required by the power plant is pumped from the reservoir to the plant.

### 4.2 Maintenance of the Dam

The dam is maintained by Missouri Power and Light personnel. Maintenance, however, is poor at the damsite. The dam and appurtenant structures are in a deteriorated condition due, primarily, to lack of maintenance. Some of the observations of conditions requiring remedial measures are given in Section 3.2 of this report.

### 4.3 Maintenance of Operating Facilities

The interior of the pumping station and the pump were inspected. The station is also used as a storage building. The station is clean and, considering its age, in reasonably good condition. Since the pump is only used intermittently, the station is normally unattended and locked. The most recent operation of the pump was in the spring of 1978. The supply sump was inspected; its water surface was clean. The intake pipes were not observed since they are under water.

4.4        Description of Any Warning System in Effect

The inspection team is not aware of any existing warning system for this dam.

4.5        Evaluation

Maintenance of the dam and appurtenant structures is very poor. The embankment section and spillway is in a badly deteriorated condition, and remedial measures will be required. No problems are apparent with the operating procedures at the damsite.

## SECTION 5: HYDRAULIC/HYDROLOGIC

### 5.1 Evaluation of Features

#### a. Design

Missouri Power and Light Dam has a watershed of approximately 769 acres. This area is approximately 5 percent covered with brush and forest. Land gradients average about 1.5 to 2.5 percent.

Elevations within the watershed range from approximately 792 feet above MSL at the damsite to over 835 feet above MSL in the upper portion of the watershed.

A drainage map showing the watershed area is included in Appendix B.

Evaluation of the hydraulic and hydrologic features of Missouri Power and Light Dam was based on criteria set forth in the Corps of Engineers' Recommended Guidelines for Safety Inspection of Dams, and additional guidance provided by the St. Louis District of the Corps of Engineers. The Probable Maximum Flood (PMF) was calculated from the Probable Maximum Precipitation (PMP) using the methods outlined in the U.S. Weather Bureau Publication, Hydrometeorological Report No. 33. The probable maximum storm duration was set at 24 hours, and storm rainfall distribution was based on criteria given in EM 1110-2-1411 (Standard Project Storm). The SCS triangular hydrograph, transformed to a curvilinear hydrograph, was adopted for developing the unit hydrograph. The derived unit hydrograph is presented in Appendix B.

Initial and infiltration loss rates were applied to the PMF to obtain rainfall excesses. The rainfall excesses were then applied to the unit hydrograph to obtain the PMF hydrograph, utilizing the Corps of Engineers' computer program HEC-1, (Dam Safety Version), which was prepared specifically for dam safety analysis. The computed peak discharge of the PMF and one-half of the PMF are 8,551 cfs and 4,276 cfs, respectively. The spillway hydraulic capacity just before overtopping of the dam is 867 cfs.

Both the PMF and one-half of the PMF inflow hydrographs were routed through the reservoir by the Modified Puls Method, also utilizing the HEC-1 (Dam Safety Version) computer program. The peak outflow discharges for the PMF and one-half of the PMF are 7,854 cfs and 3,927 cfs, respectively. Both the PMF and one-half of the PMF, when routed through the reservoir, resulted in overtopping of the dam.

The stage-outflow relation for the spillway was prepared from field notes and sketches. The reservoir stage-capacity data were based on the U.S.G.S. quadrangle topographic maps in combination with data given in the National Dam Safety Inventory Table. Reservoir storage capacity included surcharge levels exceeding the top of the dam, and the spillway overtop rating curve assumed that the dam remains intact during routing. In the routing computations, the discharge through the outlet facilities was excluded due to its insignificant magnitude as compared to the spillway discharge and the PMF. The spillway rating curve and the reservoir capacity curve are also presented in Appendix B.

From the standpoint of dam safety, the hydrologic design of a dam aims at avoiding overtopping. Overtopping is especially dangerous for an earth dam because the downrush of waters over the crest will erode the dam face and, if continued long enough, will breach the dam embankment and release all the stored water suddenly into the downstream floodplain. The safe hydrologic design of a dam calls for a spillway discharge capability, in combination with an embankment crest height that can handle a very large and exceedingly rare flood without overtopping.

The Corps of Engineers designs its dams to safely pass the Probable Maximum Flood that is estimated could be generated from the upstream watershed. This is the generally accepted criterion for major dams throughout the world, and is the standard for dam safety where overtopping would pose any threat to human life. Although dams that do not fully meet this standard will not be evaluated as "unsafe", the Corps considers the minimum hydrologic requirement for safety for this dam to be the capability to pass one-half of the Probable Maximum Flood without overtopping.

b. Experience Data

No records of reservoir stage or spillway discharge are maintained for this site. However, according to interviews with local residents, the maximum reservoir level was never higher than the crest of the embankment.

c. Visual Observations

The entire structure demonstrates a lack of adequate maintenance. Concrete in the spillway is in a deteriorated condition. Severe erosion and spalling, as well as diagonal cracks were observed in the spillway structure. Debris and aquatic growth were noted in the spillway approach channel. The downstream channel has not been adequately maintained, and the channel banks show signs of instability. The downstream channel is not capable of passing the SDF without overtopping the channel banks.

d. Overtopping Potential

As indicated in Section 5.1-a., both the Probable Maximum Flood and one-half of the Probable Maximum Flood, when routed through the reservoir, resulted in overtopping of the dam. The PMF and one-half of the PMF overtopped the dam crest by 2.31 feet and 1.12 feet, respectively. The total duration of embankment overflow is 6.10 hours during the PMF, and 4.20 hours during one-half of the PMF. The spillway of the Missouri Power and Light Dam is capable of passing a flood equal to approximately 17 percent of the PMF just before overtopping the dam. The 100-year flood is equal to approximately 9 percent of the PMF, therefore, the spillway will pass the 100-year flood without overtopping of the dam. Since one-half of the PMF is the minimum Spillway Design Flood (SDF) for Missouri Power and Light Dam, according to the Recommended Guidelines for Safety Inspection of Dams by the Corps, the spillway capacity of the dam is considered "Inadequate".

The effect from rupture of the dam could extend approximately two miles downstream of the dam. There are four farmhouses, one church and related buildings, three county roads, and one U.S. highway within the four miles of floodplain area.



## SECTION 6: STRUCTURAL STABILITY

### 6.1 Evaluation of Structural Stability

#### a. Visual Observations

The following visual observations affect the structural stability of the dam embankment.

1. Lack of proper compaction of the reconstructed embankment section.
2. Steep downstream slope which is overgrown with brush and trees. Also, some indication of seepage is present on the slope, but is hard to identify due to heavy vegetation.
3. Generally unstable rock wall protecting the upstream slope.
4. Extensive rodent activity throughout the embankment section.
5. Indications of seepage on the downstream embankment slope and below the toe of the dam in various areas.
6. The deteriorated condition of the concrete spillway. This spillway section washed out once in 1911.

No problems exist with the pumping plant which affect the structural stability of the dam.

b. Design and Construction Data

No design or construction data relating to the structural stability of the dam or appurtenant structures are available. The design data relating to seepage and stability analyses are known to exist.

c. Operating Records

No operating records are available relating to the stability of the dam or appurtenant structures. The reservoir had not yet refilled following the repair work done in July, 1978, on the embankment section. Normal operation of the reservoir would have the water level close to full at all times.

d. Post Construction Changes

Work performed after the original construction included reconstruction of a washed out spillway in 1911, and the recent repair to the embankment section.

e. Seismic Stability

In general, projects located in Seismic Zones 0, 1 and 2 can be assumed to present no hazard from earthquake, provided the static stability conditions are satisfactory and conventional safety margins exist. Missouri Power and Light Dam is located in Seismic Zone 1. A detailed seismic analysis is not felt to be necessary for this embankment.

## SECTION 7: ASSESSMENT/REMEDIAL MEASURES

### 7.1 Dam Assessment

The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

It should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team.

It is also important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that an unsafe condition could be detected.

#### a. Safety

The overall safety of Missouri Power and Light Dam is considered poor. The spillway capacity was found to be seriously inadequate. The spillway is capable of passing a flood equal to only 17 percent of the PMF. In addition, the embankment is in a deteriorated condition. The downstream embankment slope is generally very steep, and exhibits sloughing in many areas. Some seepage ponds and phreatophytes were observed downstream of the toe of the dam in the vicinity of

the former river channel. Also, vegetation, indicating moisture, was observed on the downstream slope itself in many areas. A large amount of trees and brush cover the slope, making proper inspection virtually impossible. The upstream slope is protected by an unstable 4-foot high rock wall, which has failed in several areas, and appears to be on the verge of failure in other areas.

The repaired section of embankment is of questionable stability. The compaction of the earthfill is likely not satisfactory, based on visual observation and the reported method of compaction. The section was also replaced with a steep slope corresponding to the remainder of the embankment. A rodent hole was reported to be the cause for the leak which initiated the repairs. Rodent activity is prevalent on the embankment.

The concrete spillway structure is also in deteriorated condition. A large amount of cracking, spalling and erosion was observed on the concrete slab and walls. The spillway washed out in 1911, and was replaced with the current structure at that time.

The questionable safety of this dam is compounded by the serious hazard potential downstream of the embankment. The reservoir and dam is located in an urban area, with a church, houses and 4 roads located downstream of the dam.

b. Adequacy of Information

Information concerning operation and maintenance of the dam and appurtenant structures is lacking. It is recommended that the following programs be initiated to help alleviate this problem:

1. Annual inspection of the dam by a professional engineer experienced in the design and construction of earthen dams should be made and this report made a matter of record.
2. Set up a maintenance schedule and log all visits to the dam for operation, repairs and maintenance.
3. Assemble and keep on hand complete documentation of the dam design, as-built drawings, and any other data pertaining the the dam safety.
4. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams".

c. Urgency

The remedial measures recommended in Paragraph 7.2 should be accomplished in the near future.

Increasing the spillway capacity and performing the embankment stability study is more urgent nature than the other recommended actions.

d. Necessity for Phase II Inspection

Based on results of the Phase I inspection, and if the remedial measures recommended in Paragraph 7.2 are undertaken as soon as possible, a Phase II inspection is not felt to be necessary.

## 7.2 Remedial Measures

### a. Alternatives

Possible alternatives for increasing the spillway capacity of the dam include:

1. Widening the existing spillway.
2. Lowering the existing spillway.
3. Raising the dam crest.
4. Combination of above.

A comprehensive stability study of the embankment section is recommended. This study should include determination of the embankment cross-section by survey, drilling of test holes into the embankment and foundation to provide information about the embankment and foundation condition and, possibly, the installation of piezometers to locate the phreatic line for the embankment section. The study should also analyze the recently repaired section of embankment in detail, with recommendations.

### b. O & M Maintenance Procedures


The owner should initiate the following programs:

1. Annual inspection of the dam by a professional engineer experience in the design and construction of earthen dams.


2. Set up a maintenance schedule and log all visits to the dam for operation, repairs and maintenance.
3. Assemble and keep on hand complete documentation of the dam design, as-built drawings, and any other data pertaining to the dam safety.
4. Clear large trees and brush from the downstream embankment slope, and prevent future growth by frequent maintenance.
5. Make repairs, as necessary, to the upstream slope, including strengthening areas currently exhibiting instability.
6. Eliminate rodents currently burrowing into the embankment, and fill holes with compacted earthfill to the extent possible.
7. Make repairs to the deteriorated concrete in the spillway structure and stabilize the downstream channel slopes.
8. Clear the obstructions from the downstream channel.
9. Seepage and stability analysis should be performed by a professional engineer experience in the design and construction of dams.

PLATES







LOCATION MAP  
MISSOURI POWER & LIGHT DAM  
AUDRAIN COUNTY, MISSOURI



PLAN




ELEVATION LOOKING DOWNSTREAM



SECTION A-A  
(THROUGH SPILLWAY)

SCALE:  
1" = 100' (HORIZONTAL)  
VERTICAL (NOT TO SCALE)

# MISSOURI POWER & LIGHT DAM RELATIVE ELEVATIONS



### Explanation

#### Pennsylvanian System

- P<sub>kc</sub> - Kansas City group: cyclic deposits with numerous limestones.
- P<sub>pwm</sub> - Pleasanton group: sandstone channel member.
- P<sub>m</sub> - Marmaton group: cyclic deposits with limestones.
- P<sub>cc</sub> - Cherokee group: cyclic deposits, predominately shale, sandstone and coal beds.

#### Mississippian System

- M<sub>m</sub> - sandy, oolitic, fossiliferous, lithographic, or cherty limestones.
- M<sub>o</sub> - cherty, crinoidal limestone, with some shale.
- M<sub>k</sub> - intercalated limestones and shales.

#### Devonian System

- D - limestones and sandstones.

#### Silurian System

- S - limestones with some shale and chert.

#### Ordovician System

- O<sub>mk</sub> - shale and limestones.
- O<sub>dp</sub> - shale with thin fossiliferous limestone beds and dense limestone.

Reference: Geologic Map of Missouri, 1961, Division of Geological Survey and Water Resources, State of Missouri.

APPENDIX A

PHOTOGRAPHS TAKEN DURING INSPECTION

MISSOURI POWER AND LIGHT DAM

- Photo 1 - View along crest of dam taken near left side of dam.
- Photo 2 - View along upstream slope of embankment taken at left abutment of dam.
- Photo 3 - Picture of typical section of upstream embankment slope near left side of dam.
- Photo 4 - Picture of upstream embankment slope taken on upstream slope near center of dam.
- Photo 5 - Close-up of section of upstream embankment slope exhibiting sloughing.
- Photo 6 - Picture of rodent hole behind blocks on upstream embankment slope.
- Photo 7 - Picture of rodent hole behind blocks on upstream embankment slope.
- Photo 8 - Picture of downstream embankment slope taken downstream of dam near right abutment.
- Photo 9 - Picture of repaired embankment as seen on dam crest.
- Photo 10 - Picture of repaired section of embankment taken from crest looking downstream.
- Photo 11 - Picture of spillway approach channel taken from dam crest.
- Photo 12 - Picture of entrance to spillway taken from left abutment of dam.
- Photo 13 - Picture of spillway taken from downstream.
- Photo 14 - View of spillway discharge channel taken at crest of spillway.
- Photo 15 - Close-up of typical cracked areas on the spillway channel side walls.
- Photo 16 - Close-up of eroded concrete at upstream end of concrete spillway crest.

Missouri Power and Light Dam



Photo 1 - View along crest of dam taken near left side of dam.



Photo 2 - View along upstream slope of embankment taken at left abutment of dam.

Missouri Power and Light Dam



Photo 3 - Picture of typical section of upstream embankment slope near left side of dam.



Photo 4 - Picture of upstream embankment slope taken on upstream slope near center of dam.



Photo 5 - Close-up of section of upstream embankment slope exhibiting sloughing.



Photo 6 - Picture of rodent hole behind blocks on upstream embankment slope.





Photo 7 - Picture of rodent hole behind blocks on upstream embankment slope.



Photo 8 - Picture of downstream embankment slope taken downstream of dam near right abutment.

Missouri Power and Light Dam



Photo 9 - Picture of repaired section of embankment as seen on the dam crest.



Photo 10 - Picture of repaired section of embankment taken from crest looking downstream.

Missouri Power and Light Dam



Photo 11 - Picture of spillway approach channel taken from dam crest.



Photo 12 - Picture of entrance to spillway taken from left abutment of dam.

Missouri Power and Light Dam



Photo 13 - Picture of spillway taken from downstream.



Photo 14 - View of spillway discharge channel taken at crest of spillway.




Photo 15 - Close-up of typical cracked areas on the spillway channel side walls.



Photo 16 - Close-up of eroded concrete at upstream end of concrete spillway crest.


APPENDIX B

HYDROLOGIC COMPUTATIONS




CONTOUR INTERVAL 10 FEET  
DATUM IS MEAN SEA LEVEL  
DRAINAGE BOUNDARY - - -

## MISSOURI POWER & LIGHT DAM DRAINAGE AREA



MISSOURI POWER AND LIGHT DAM  
RESERVOIR CAPACITY CURVE





MISSOURI POWER & LIGHT DAM  
SPILLWAY & OVERTOP RATING CURVE

## ENGINEERING CONSULTANTS, INC.

DAM SAFETY INSPECTION - MISSOURI

SHEET NO. 1 OF

MISSOURI POWER AND LIGHT DAM

JOB NO. 1223-001-1

RESERVOIR AREA CAPACITY

BY KLB DATE 10-11-78

MISSOURI POWER AND LIGHTRESERVOIR AREA CAPACITY

The data used are based on USGS Mexico West Quadrangle  
Sheet (7.5 minute series) in combination with data given in the National  
Dam Safety Inventory Table.

ELEV. M. S. L. (FT)	RESERVOIR SURFACE AREA (ACRES)	INCREMENTAL VOLUME (AC-FT)	TOTAL VOLUME (AC-FT)	REMARKS
772	0	-	0	STREAMBED AT CENTER OF DAM
792	28	224	224	SPINWAY CREST
795.67	30	106	330	TOP OF DAM
800	49	171	501	
810	112	805	1306	
820	237	1745	3051	

# ENGINEERING CONSULTANTS, INC.

DAM SAFETY INSPECTION / MISSOURI

SHEET NO. 1 OF 2


MO. POWER & LIGHT DAM

JOB NO. 122B-001

SPILLWAY & OVERTOP DISCHARGE CAPACITY

BY MAS

DATE 10-10-78



Upstream W.S. EL. (ft)	H <sub>1</sub> (ft)	H <sub>2</sub> (ft)	L <sub>1</sub> (ft)	L <sub>2</sub> (ft)	C <sub>1</sub>	C <sub>2</sub>	$Q = \sum_{i=1}^2 C_i L_i H_i^{1.5}$ (cfs)
792	0						
793	1		46		2.68		123
794	2		46		2.65		345
795.67	3.67	0	46		2.68		867
796	4	0.33	46	637	2.70	2.70	994 + 326 = 1320
798	6	2.33	46	637	2.88	2.63	1947 + 5958 = 7905
800	8	4.33	46	637	2.88	2.63	2998 + 15095 = 18093
805	13	9.33	46	637	2.88	2.63	6210 + 47744 = 53954

# ENGINEERING CONSULTANTS, INC.

DAM SAFETY INSPECTION - MISSOURI

SHEET NO. 1 OF

MISSOURI POWER AND LIGHT DAM

JOB NO. 1223-001-1

UNIT HYDROGRAPH PARAMETERS

BY HLB DATE 7-78

1. DRAINAGE AREA, = 769 ACRES = 1.20 SQ. MI.

2. LENGTH OF STREAM =  $L = (3.2' \times 2000' / 5280') = 1.21 \text{ MI.}$

3. DIFFERENCE IN ELEVATION:  $\Delta H$

$\Delta H = 835 - 792 = 43 \text{ FT.}$

4. TIME OF CONCENTRATION

$$T_c = \left( \frac{11.9 \times L^3}{\Delta H} \right)^{0.385} = \left( \frac{11.9 \times 1.21^3}{43} \right)^{0.385}$$

$T_c = 0.76 \text{ HR.}$

5. LAG TIME  $L_t = 0.6 \times T_c$

$L_t = 0.6 \times 0.76 = 0.46 \text{ HR}$

6. UNIT DURATION  $D = \frac{L_t}{3} = \frac{0.46}{3} = 0.15$

USE  $D = 0.10 \text{ HR}$

7. TIME TO PEAK,  $T_p$

$T_p = \frac{D}{2} + 0.6 \times T_c = \frac{0.10}{2} + 0.6 \times 0.76$

$T_p = 0.51 \text{ HR}$

8.  $q_p = \frac{484 \cdot A}{T_p} = \frac{484 \times 1.20}{0.51} = 1138.82 \text{ CFS}$

DAM SAFETY INSPECTION - MISSOURI

SHEET NO. 2 OF

MISSOURI POWER AND LIGHT

JOB NO. 1223-001-1

UNIT HYDROGRAPH DERIVATION


BY HLB

DATE 10-10-78

7) CURVILINEAR UNIT HYDROGRAPH

TIME $T/T_p$	DISCHARGE RATIO $Q/Q_p$	UNIT HYDROGRAPH	
		TIME, T (HOURS)	DISCHARGE (CFS)
0.00	0.000	0.00	0.000
0.1	0.015	0.05	17.08
0.2	0.075	0.10	85.41
0.3	0.16	0.15	182.21
0.4	0.28	0.20	318.87
0.5	0.45	0.26	512.47
0.6	0.60	0.31	683.29
0.7	0.77	0.36	876.89
0.8	0.89	0.41	1013.55
0.9	0.97	0.46	1104.56
1.0	1.00	0.51	1138.82
1.1	0.98	0.56	1116.04
1.2	0.92	0.61	1047.71
1.3	0.84	0.66	956.61
1.4	0.75	0.71	854.12
1.5	0.66	0.77	751.62
1.6	0.56	0.82	637.74
1.8	0.42	0.92	478.30
2.0	0.32	1.02	364.42
2.2	0.24	1.12	273.32
2.4	0.18	1.22	204.77
2.6	0.13	1.33	148.05
2.8	0.098	1.43	111.60
3.0	0.075	1.53	85.41
3.5	0.036	1.77	41.90
4.0	0.018	2.04	20.50
4.5	0.009	2.30	10.25
5.0	0.004	2.55	4.56

785



MISSOURI POWER AND LIGHT DAM  
0.10 HOUR UNIT HYDROGRAPH

DAM SAFETY INSPECTION/MISSOURI

SHEET NO. 1 OF

MO. POWER &amp; LIGHT DAM

JOB NO. 1223-001

PROPOSED MAXIMUM STORM (PMS)

BY MAS DATE

MO. POWER AND LIGHT DAMDETERMINATION OF PMS

1. Determine drainage area of the basin

$$D.A. = 1.20 \text{ Sq. mi.}$$

2. Determine PMP Index Rainfall:

Location of centroid of basin:

$$\text{Long. } 91.9^\circ; \text{ Lat. } 39.16^\circ$$

$$\rightarrow \text{PMP for } 200 \text{ Sq. mi. \& 24 hrs duration} \\ = 24.7" (\text{from Fig 1, HMR NO 33})$$

3. Determine basin rainfall in terms of percentage of PMP Index rainfall for various durations:

$$\text{Location: Long. } 91.9^\circ; \text{ Lat. } 39.16^\circ$$

$$\Rightarrow \text{Zone 7}$$

Duration (Hrs.)	Percent of Index rainfall (%)	Total rainfall (Inches)	Rain-fall increments (Inches)	Duration of incre- ment (Hrs.)
6	100	24.7	24.7	6
12	120	29.6	4.9	6
24	130	32.1	2.5	12

# ENGINEERING CONSULTANTS, INC.

DAM SAFETY INSPECTION / MISSOURI SHEET NO. 1 OF  
 MO. POWER AND LIGHT DAM JOB NO. 1223-001  
 - 100-YEAR FLOOD BY REGRESSION EQUATION BY MAS DATE 10-20-78

## MO. POWER AND LIGHT DAM

### 100-YEAR FLOOD BY REGRESSION EQUATION

Regression equation for 100-year flood for Missouri:

$$Q_{100} = 85.1 A^{0.934} S^{-0.02} S^{0.576}$$

Where, A = drainage area in sq. mi.

S = main channel slope ft./mi.

(Avg. slope between 0.14 & 0.854)

For Mo. Power & Light Dam:

$$A = 769 \text{ acres} = 1.20 \text{ sq. mi.}$$

$$S = 28 \text{ ft.} / 0.91 \text{ mi} = 30.85 \text{ ft.} / \text{mi}$$

$$Q_{100} = 85.1 (1.20)^{0.934} (1.20)^{-0.02} (30.85)^{0.576}$$

$$= \underline{\underline{727 \text{ cfs}}}$$



HEC1DB INPUT DATA

[illegible]

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS

RUNOFF HYDROGRAPH AT 8  
ROUTE HYDROGRAPH TO 8  
END OF NETWORK

INFLOW PMF AND ONE-HALF PMF HYDROGRAPHS

\*\*\*\*\*  
 FLOOD HYDROGRAPH PACKAGE (HEC-1)  
 DAM SAFETY VERSION JULY 1974  
 LAST MODIFICATION 3 AUG 74  
 \*\*\*\*\*

RUN DATE: 7/10/74.  
 TIME: 13.02.17.

DAM SAFETY INSPECTION - MISSOURI  
 MISSOURI POWER AND LIGHT DAM  
 PMF AND 50 PERCENT PMF DETERMINATION AND ROUTING

JPM SPECIFICATION									
NO	AMP	AMP%	IPAY	IPW	IPW%	WTPE	WT%	IPDT	ASTAY
500	0	6	0	0	0	0	0	0	0
			INPEW	NMT	UNDT	TRAF			
			5	0	0	0			

MULTI-PLAN ANALYSIS TO BE PERFORMED  
 NPLANE 1 ARTICE 2 LRTIME 1

RTIME= 1.00 .50

\*\*\*\*\*

SUB-AREA RUNOFF COMPUTATION

INPUT PMF INDEX PRECIPITATION AND RATIOS, INPUT SECTION  
 ISTAT ICOMP ITCN ITAPE JPLY JPLY INAME ISTAT IAUO

HYDROGRAPH DATA									
IMYD	IMYD	TAREA	SNAP	THSDA	THSPC	RATIO	ISYD	ISAME	LOCAL
1	-1	1.20	0.00	1.20	1.00	0.000	0	0	0

PRECIP DATA									
SPPE	PMS	PH	P12	P24	P48	P72	P96		
0.00	24.70	100.00	120.00	130.00	0.00	0.00	0.00		

LOSS DATA									
LRPPT	STRKR	DLTKR	RTLO	ERAIN	STRKS	RTLOK	STPIL	CNSTL	ALSMX
0	0.00	0.00	1.00	0.00	0.00	1.00	.85	.07	0.00

GIVEN UNIT GRAPH, NUMGE= 27  
 80. 280. 655. 970. 1119. 1060. 895. 680. 510.  
 305. 220. 165. 125. 88. 60. 40. 22. 15.  
 7. 5. 3. 2. 1. 0. 0. 0. 0.

UNIT GRAPH TOTALS 7712. CFS OR 1.00 INCHES OVER THE AREA

RECESSION DATA  
 STRIDE 0.00 ORCSN= 0.00 RTIME= 1.00  
 END-OF-PERIOD FLOW MU,DA HR,MM PERIOD RAIN EXCS LOSS COMP 0

1.01	.06	1	.02	0.00	.02	0.	1.01	15.15	151	.38	.57	.01	2720.
1.01	.12	2	.02	0.00	.02	0.	1.01	15.12	152	.47	.46	.01	2747.
1.01	.18	3	.02	0.00	.02	0.	1.01	15.18	153	.56	.56	.01	2772.
1.01	.24	4	.02	0.00	.02	0.	1.01	15.24	154	.75	.74	.01	2821.
1.01	.30	5	.02	0.00	.02	0.	1.01	15.30	155	1.69	1.68	.01	2938.
1.01	.36	6	.02	0.00	.02	0.	1.01	15.36	156	3.00	3.00	.01	3231.
1.01	.42	7	.02	0.00	.02	0.	1.01	15.42	157	.94	.93	.01	3929.
1.01	.48	8	.02	0.00	.02	0.	1.01	15.48	158	.75	.74	.01	5143.
1.01	.54	9	.02	0.00	.02	0.	1.01	15.54	159	.47	.46	.01	6723.
1.01	1.00	10	.02	0.00	.02	0.	1.01	16.00	160	.38	.37	.01	7949.
1.01	1.06	11	.02	0.00	.02	0.	1.01	16.06	161	.55	.54	.01	8551.
1.01	1.12	12	.02	0.00	.02	0.	1.01	16.12	162	.35	.34	.01	8251.
1.01	1.18	13	.02	0.00	.02	0.	1.01	16.18	163	.35	.34	.01	7480.
1.01	1.24	14	.02	0.00	.02	0.	1.01	16.24	164	.35	.34	.01	6496.
1.01	1.30	15	.02	0.00	.02	0.	1.01	16.30	165	.35	.34	.01	5613.
1.01	1.36	16	.02	0.00	.02	0.	1.01	16.36	166	.35	.34	.01	4899.
1.01	1.42	17	.02	0.00	.02	0.	1.01	16.42	167	.35	.34	.01	4347.
1.01	1.48	18	.02	0.00	.02	0.	1.01	16.48	168	.35	.34	.01	1913.
1.01	1.54	19	.02	0.00	.02	0.	1.01	16.54	169	.35	.34	.01	3587.
1.01	2.00	20	.02	0.00	.02	0.	1.01	17.00	170	.35	.34	.01	3335.
1.01	2.06	21	.02	0.00	.02	0.	1.01	17.06	171	.27	.26	.01	3128.
1.01	2.12	22	.02	0.00	.02	0.	1.01	17.12	172	.27	.26	.01	2964.
1.01	2.18	23	.02	0.00	.02	0.	1.01	17.18	173	.27	.26	.01	2825.
1.01	2.24	24	.02	0.00	.02	0.	1.01	17.24	174	.27	.26	.01	2685.
1.01	2.30	25	.02	0.00	.02	0.	1.01	17.30	175	.27	.26	.01	2563.
1.01	2.36	26	.02	0.00	.02	0.	1.01	17.36	176	.27	.26	.01	2445.
1.01	2.42	27	.02	0.00	.02	0.	1.01	17.42	177	.27	.26	.01	2346.
1.01	2.48	28	.02	0.00	.02	0.	1.01	17.48	178	.27	.26	.01	2266.
1.01	2.54	29	.02	0.00	.02	0.	1.01	17.54	179	.27	.26	.01	2205.
1.01	3.00	30	.02	0.00	.02	0.	1.01	18.00	180	.27	.26	.01	2160.
1.01	3.06	31	.02	0.00	.02	0.	1.01	18.06	181	.02	.02	.01	2126.
1.01	3.12	32	.02	0.00	.02	0.	1.01	18.12	182	.02	.02	.01	2080.
1.01	3.18	33	.02	0.00	.02	0.	1.01	18.18	183	.02	.02	.01	1993.
1.01	3.24	34	.02	0.00	.02	0.	1.01	18.24	184	.02	.02	.01	1819.
1.01	3.30	35	.02	0.00	.02	0.	1.01	18.30	185	.02	.02	.01	1570.
1.01	3.36	36	.02	0.00	.02	0.	1.01	18.36	186	.02	.02	.01	1242.
1.01	3.42	37	.02	0.00	.02	0.	1.01	18.42	187	.02	.02	.01	1016.
1.01	3.48	38	.02	0.00	.02	0.	1.01	18.48	188	.02	.02	.01	792.
1.01	3.54	39	.02	0.00	.02	0.	1.01	18.54	189	.02	.02	.01	622.
1.01	4.00	40	.02	0.00	.02	0.	1.01	19.00	190	.02	.02	.01	495.
1.01	4.06	41	.02	0.00	.02	0.	1.01	19.06	191	.02	.02	.01	399.
1.01	4.12	42	.02	0.00	.02	0.	1.01	19.12	192	.02	.02	.01	326.
1.01	4.18	43	.02	0.00	.02	0.	1.01	19.18	193	.02	.02	.01	271.
1.01	4.24	44	.02	0.00	.02	0.	1.01	19.24	194	.02	.02	.01	230.
1.01	4.30	45	.02	0.00	.02	0.	1.01	19.30	195	.02	.02	.01	199.
1.01	4.36	46	.02	0.00	.02	0.	1.01	19.36	196	.02	.02	.01	177.
1.01	4.42	47	.02	0.00	.02	0.	1.01	19.42	197	.02	.02	.01	162.
1.01	4.48	48	.02	0.00	.02	0.	1.01	19.48	198	.02	.02	.01	153.
1.01	4.54	49	.02	0.00	.02	0.	1.01	19.54	199	.02	.02	.01	147.
1.01	5.00	50	.02	0.00	.02	0.	1.01	20.00	200	.02	.02	.01	143.
1.01	5.06	51	.02	0.00	.02	0.	1.01	20.06	201	.02	.02	.01	141.
1.01	5.12	52	.02	0.00	.02	0.	1.01	20.12	202	.02	.02	.01	139.
1.01	5.18	53	.02	0.00	.02	0.	1.01	20.18	203	.02	.02	.01	138.
1.01	5.24	54	.02	0.00	.02	0.	1.01	20.24	204	.02	.02	.01	137.
1.01	5.30	55	.02	0.00	.02	0.	1.01	20.30	205	.02	.02	.01	137.
1.01	5.36	56	.02	0.00	.02	0.	1.01	20.36	206	.02	.02	.01	137.
1.01	5.42	57	.02	0.00	.02	0.	1.01	20.42	207	.02	.02	.01	137.
1.01	5.48	58	.02	0.00	.02	0.	1.01	20.48	208	.02	.02	.01	137.
1.01	5.54	59	.02	0.00	.02	0.	1.01	20.54	209	.02	.02	.01	137.
1.01	6.00	60	.02	0.00	.02	0.	1.01	21.00	210	.02	.02	.01	137.

1.01	6.08	61	.0A	.01	56.	1.01	21.06	211	.02	.01	137.
1.01	6.12	62	.0A	.01	46.	1.01	21.12	212	.02	.01	137.
1.01	6.14	63	.0A	.01	4A.	1.01	21.14	213	.02	.01	137.
1.01	6.24	64	.0A	.01	133.	1.01	21.24	214	.02	.01	137.
1.01	6.30	65	.0A	.01	149.	1.01	21.30	215	.02	.01	137.
1.01	6.36	66	.0A	.01	176.	1.01	21.36	216	.02	.01	137.
1.01	6.42	67	.0A	.01	347.	1.01	21.42	217	.02	.01	137.
1.01	6.48	68	.0A	.01	406.	1.01	21.48	218	.02	.01	137.
1.01	6.54	69	.0A	.01	451.	1.01	21.54	219	.02	.01	137.
1.01	7.00	70	.0A	.01	444.	1.01	22.00	220	.02	.01	137.
1.01	7.04	71	.0A	.01	511.	1.01	22.06	221	.02	.01	137.
1.01	7.12	72	.0A	.01	540.	1.01	22.12	222	.02	.01	137.
1.01	7.18	73	.0A	.01	545.	1.01	22.18	223	.02	.01	137.
1.01	7.24	74	.0A	.01	566.	1.01	22.24	224	.02	.01	137.
1.01	7.31	75	.0A	.01	564.	1.01	22.30	225	.02	.01	137.
1.01	7.36	76	.0A	.01	571.	1.01	22.36	226	.02	.01	137.
1.01	7.42	77	.0A	.01	574.	1.01	22.42	227	.02	.01	137.
1.01	7.48	78	.0A	.01	577.	1.01	22.48	228	.02	.01	137.
1.01	7.54	79	.0A	.01	574.	1.01	22.54	229	.02	.01	137.
1.01	8.00	80	.0A	.01	579.	1.01	23.00	230	.02	.01	137.
1.01	8.06	81	.0A	.01	580.	1.01	23.06	231	.02	.01	137.
1.01	8.12	82	.0A	.01	584.	1.01	23.12	232	.02	.01	137.
1.01	8.14	83	.0A	.01	541.	1.01	23.14	233	.02	.01	137.
1.01	8.24	84	.0A	.01	541.	1.01	23.24	234	.02	.01	137.
1.01	8.30	85	.0A	.01	542.	1.01	23.30	235	.02	.01	137.
1.01	8.36	86	.0A	.01	541.	1.01	23.36	236	.02	.01	137.
1.01	8.42	87	.0A	.01	541.	1.01	23.42	237	.02	.01	137.
1.01	8.48	88	.0A	.01	541.	1.01	23.48	238	.02	.01	137.
1.01	8.54	89	.0A	.01	541.	1.01	23.54	239	.02	.01	137.
1.01	9.00	90	.0A	.01	541.	1.02	0.00	240	.02	.01	137.
1.01	9.06	91	.0A	.01	541.	1.02	.06	241	.00	0.00	137.
1.01	9.12	92	.0A	.01	541.	1.02	.12	242	.00	0.00	135.
1.01	9.18	93	.0A	.01	541.	1.02	.18	243	.00	0.00	130.
1.01	9.24	94	.0A	.01	541.	1.02	.24	244	.00	0.00	119.
1.01	9.30	95	.0A	.01	541.	1.02	.30	245	.00	0.00	101.
1.01	9.36	96	.0A	.01	541.	1.02	.36	246	.00	0.00	61.
1.01	9.42	97	.0A	.01	541.	1.02	.42	247	.00	0.00	62.
1.01	9.48	98	.0A	.01	541.	1.02	.48	248	.00	0.00	47.
1.01	9.54	99	.0A	.01	541.	1.02	.54	249	.00	0.00	35.
1.01	10.00	100	.0A	.01	541.	1.02	1.00	250	.00	0.00	26.
1.01	10.06	101	.0A	.01	541.	1.02	1.06	251	.00	0.00	19.
1.01	10.12	102	.0A	.01	541.	1.02	1.12	252	.00	0.00	14.
1.01	10.18	103	.0A	.01	541.	1.02	1.18	253	.00	0.00	10.
1.01	10.24	104	.0A	.01	541.	1.02	1.24	254	.00	0.00	7.
1.01	10.30	105	.0A	.01	541.	1.02	1.30	255	.00	0.00	4.
1.01	10.36	106	.0A	.01	541.	1.02	1.36	256	.00	0.00	3.
1.01	10.42	107	.0A	.01	541.	1.02	1.42	257	.00	0.00	2.
1.01	10.48	108	.0A	.01	541.	1.02	1.48	258	.00	0.00	1.
1.01	10.54	109	.0A	.01	541.	1.02	1.54	259	.00	0.00	0.
1.01	11.00	110	.0A	.01	541.	1.02	2.00	260	.00	0.00	0.
1.01	11.06	111	.0A	.01	541.	1.02	2.06	261	.00	0.00	0.
1.01	11.12	112	.0A	.01	541.	1.02	2.12	262	.00	0.00	0.
1.01	11.18	113	.0A	.01	541.	1.02	2.18	263	.00	0.00	0.
1.01	11.24	114	.0A	.01	541.	1.02	2.24	264	.00	0.00	0.
1.01	11.30	115	.0A	.01	541.	1.02	2.30	265	.00	0.00	0.
1.01	11.36	116	.0A	.01	541.	1.02	2.36	266	.00	0.00	0.
1.01	11.42	117	.0A	.01	541.	1.02	2.42	267	.00	0.00	0.
1.01	11.48	118	.0A	.01	541.	1.02	2.48	268	.00	0.00	0.
1.01	11.54	119	.0A	.01	541.	1.02	2.54	269	.00	0.00	0.
1.01	12.00	120	.0A	.01	541.	1.02	3.00	270	.00	0.00	0.







PMF FLOOD ROUTING

100



794.7	794.7	794.7	794.8	794.8	794.9	795.1	795.3	795.5	795.7
795.9	796.0	796.1	796.1	796.1	796.2	796.2	796.2	796.2	796.2
796.2	796.3	796.3	796.3	796.3	796.3	796.3	796.3	796.4	796.4
796.4	796.4	796.4	796.4	796.4	796.5	796.5	796.5	796.5	796.5
797.4	798.0	798.0	797.8	797.8	797.8	797.2	797.0	796.9	796.8
796.7	796.6	796.5	796.5	796.4	796.4	796.4	796.3	796.3	796.3
796.3	796.3	796.3	796.2	796.2	796.1	796.0	795.9	795.8	795.7
795.6	795.5	795.4	795.2	795.1	794.9	794.8	794.7	794.6	794.5
794.4	794.3	794.2	794.1	794.1	794.1	793.9	793.9	793.8	793.8
793.7	793.7	793.7	793.6	793.6	793.6	793.5	793.5	793.5	793.4
793.4	793.4	793.4	793.4	793.3	793.3	793.3	793.3	793.3	793.3
793.3	793.2	793.2	793.2	793.2	793.2	793.2	793.2	793.2	793.2
793.2	793.2	793.1	793.1	793.1	793.1	793.1	793.1	793.0	793.0
793.0	793.0	792.9	792.9	792.9	792.8	792.8	792.8	792.7	792.7
792.7	792.7	792.7	792.6	792.6	792.6	792.6	792.5	792.5	792.5
792.5	792.5	792.5	792.4	792.4	792.4	792.4	792.4	792.4	792.4
792.3	792.3	792.3	792.3	792.3	792.3	792.3	792.3	792.3	792.3
792.2	792.2	792.2	792.2	792.2	792.2	792.2	792.2	792.2	792.2

PEAK OUTFLOW IS 7854. AT TIME 16.30 HOURS

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
7854	3011	959	764	230284
222	85	27	22	6521
	23.34	20.75	20.75	29.75
	592.92	755.69	755.72	755.72
	1003	1003	1003	1003
	1042	2347	2348	2348

MAXIMUM STORAGE = 421.

ONE-HALF PMF FLOOD ROUTING

STATION N, PLAN 1, RAILROAD  
ENGINEERING HYDROGRAPH ORDINATES[illegible]

265.	264.	262.	261.	260.	259.	258.	257.	256.
266.	265.	263.	262.	260.	259.	258.	257.	256.
267.	266.	264.	263.	261.	260.	259.	258.	257.
268.	267.	265.	264.	262.	261.	260.	259.	258.
269.	268.	266.	265.	263.	262.	261.	260.	259.
270.	269.	267.	266.	264.	263.	262.	261.	260.
271.	270.	268.	267.	265.	264.	263.	262.	261.
272.	271.	269.	268.	266.	265.	264.	263.	262.
273.	272.	270.	269.	267.	266.	265.	264.	263.
274.	273.	271.	270.	268.	267.	266.	265.	264.
275.	274.	272.	271.	269.	268.	267.	266.	265.
276.	275.	273.	272.	270.	269.	268.	267.	266.
277.	276.	274.	273.	271.	270.	269.	268.	267.
278.	277.	275.	274.	272.	271.	270.	269.	268.
279.	278.	276.	275.	273.	272.	271.	270.	269.
280.	279.	277.	276.	274.	273.	272.	271.	270.
281.	280.	278.	277.	275.	274.	273.	272.	271.
282.	281.	279.	278.	276.	275.	274.	273.	272.
283.	282.	280.	279.	277.	276.	275.	274.	273.
284.	283.	281.	280.	278.	277.	276.	275.	274.
285.	284.	282.	281.	279.	278.	277.	276.	275.
286.	285.	283.	282.	280.	279.	278.	277.	276.
287.	286.	284.	283.	281.	280.	279.	278.	277.
288.	287.	285.	284.	282.	281.	280.	279.	278.
289.	288.	286.	285.	283.	282.	281.	280.	279.
290.	289.	287.	286.	284.	283.	282.	281.	280.
291.	290.	288.	287.	285.	284.	283.	282.	281.
292.	291.	289.	288.	286.	285.	284.	283.	282.
293.	292.	290.	289.	287.	286.	285.	284.	283.
294.	293.	291.	290.	288.	287.	286.	285.	284.
295.	294.	292.	291.	289.	288.	287.	286.	285.
296.	295.	293.	292.	290.	289.	288.	287.	286.
297.	296.	294.	293.	291.	290.	289.	288.	287.
298.	297.	295.	294.	292.	291.	290.	289.	288.
299.	298.	296.	295.	293.	292.	291.	290.	289.
300.	299.	297.	296.	294.	293.	292.	291.	290.

[illegible]

PEAK OUTFLOW IS 3927. AT TIME 16.30 HOURS

	PEAK	6-MOURE	24-MOURE	72-MOURE	TOTAL VOLUME
CPS	392.1	1456.	479.	38.	115034.
CMS	111.	41.	14.	11.	3857.
INCHES	11.30	14.86	14.86		14.86
MM	267.10	377.49	377.50		377.50
AC-FT	723.	951.	951.		951.
THOUS CU M	692.	1173.	1173.		1173.

MAXIMUM STORAGE 2 374.



SUMMARY OF PMF AND ONE-HALF PMF FLOOD ROUTING

PEAK FLOW AND STORAGE (FAC OF PERCENT) SUMMARY FOR MULTIPLE PLANNING SCENARIO COMPUTATIONS  
 FLOWS IN CUBIC FEET PER SECOND (CFS) METERS PER SECOND  
 AREA IN SQUARE MILES (SQMI) KILOMETERS

OPERATION STATION AREA PLD RATIO 1 RATIO 2 RATIO 3 APPLICABLE FLOWS

HYDROGRAPH AT R 1.20 1 4551.4 4276.  
 ( 3.11) ( 242.10) ( 121.07) (

ROUTED TO R 1.20 1 7450. 3927.  
 ( 3.11) ( 222.39) ( 111.19) (

# SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 .....

RATIO OF DAM	ELEVATION STORAGE OUTFLOW	INITIAL ZONE 792.00 224. 0.	SPILLWAY CREST 792.00 224. 0.	TOP OF DAM 795.67 539. 867.	MAXIMUM STORAGE ACFT	MAXIMUM DEPTH OVER DAM	MAXIMUM VELOCITY CFS	DURATION HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
1.00	797.00	2.31	0.21	7850.	6.10	16.30	0.00			
0.50	796.70	1.15	374.	5027.	4.20	16.30	0.00			

.....  
FLDND HYDRO-PACKAGE (HFC-1)  
PAM SAFETY SECTION JULY 1974  
LAST MODIFICATION 3 AUG 74  
.....

PERCENT OF PMF FLOOD ROUTING  
EQUAL TO SPILLWAY CAPACITY

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS

WINDOM HYDROGRAPH AT 8  
ROUTE HYDROGRAPH TO 8  
END OF NETWORK

RUN DATE: 74/10/24.  
 TIME: 08.34.46.

CAN SAFETY INSPECTION - MISSOURI  
 MISSOURI POWER AND LIGHT CAN  
 PERCENT OF PER DETERMINATION, AND WAITING

NO.	DATE	TIME	WET W.	DRY W.	WET W. - DRY W.	WET W. - DRY W. - 100
100	10/10/10	10:00	100	100	0	0
101	10/10/10	10:00	100	100	0	0
102	10/10/10	10:00	100	100	0	0
103	10/10/10	10:00	100	100	0	0
104	10/10/10	10:00	100	100	0	0
105	10/10/10	10:00	100	100	0	0
106	10/10/10	10:00	100	100	0	0
107	10/10/10	10:00	100	100	0	0
108	10/10/10	10:00	100	100	0	0
109	10/10/10	10:00	100	100	0	0
110	10/10/10	10:00	100	100	0	0
111	10/10/10	10:00	100	100	0	0
112	10/10/10	10:00	100	100	0	0
113	10/10/10	10:00	100	100	0	0
114	10/10/10	10:00	100	100	0	0
115	10/10/10	10:00	100	100	0	0
116	10/10/10	10:00	100	100	0	0
117	10/10/10	10:00	100	100	0	0
118	10/10/10	10:00	100	100	0	0
119	10/10/10	10:00	100	100	0	0
120	10/10/10	10:00	100	100	0	0

1 JULIAN. 1300 AD.  
CITY OF NEW YORK

DATE	TIME	LOCATION	WIND	WAVE	SEA	TEMP	WIND	WAVE	SEA	TEMP
10	15	20	25	30	35	40	45	50	55	60

SHAW-WATKINS COMPANY

```
INPUT FOR INTERPREDICTION AND GATTS, INPUT SCENES
```

А.А. МАНУСОВ

IMYDG	IMG	TART4	SAAP	TUSDA	TRPC	WATN	ISNM	ISAF	LOCAL
1	-1	1.20	0.00	1.20	1.00	0.000	0	0	0

W46C1P 047A

SPF	WYS	W6	W12	W24	R74	R72	R96
0.00	24.70	100.00	120.00	130.00	0.00	0.00	0.00

**LUSS DATA**

LANDRY	STARR	DLTKM	RTTOL	FLATN	STUK9	RTTKM	SIRTL	CNSIL	ALSHK	HTTTP
0	0.00	0.00	1.00	0.00	0.00	1.00	.85	.07	0.00	0.00

ACCESSION DATA

STATICS 0.00 ANSJO 00.0 WTUN= 1.00

9118 0118 34-3100144

[illegible]

SUM	32.11	29.94	2.17	230924.
	( 116. )	( 741. )	( 55. )	( 6534.04 )





PEAK FLOW AND STORAGE TEND OF PERIODS SUMMARY FOR MULTIPLE PLANE-RATIO ECONOMIC COMPUTATIONS  
 FLOWS IN CUMIC FEET PER SECOND (CUMIC METERS PER SECOND)  
 AREA IN SQUARE FEET (SQUARE METER)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS								
				RATIO 1	RATIO 2	RATIO 3	RATIO 4	RATIO 5	RATIO 6	RATIO 7	RATIO 8	RATIO 9
HYDROGRAPH AT	A	1.20	1	855	1285	1710	2130	2565	2995	3420	3848	4276
	(	5.11)	(	24,210	36,520	48,830	60,540	72,640	84,750	96,860	108,960	121,070
ROUTED TO	A	1.20	1	435	772	1072	1405	2259	2722	3155	3533	3927
	(	3.11)	(	12,520	19,240	27,370	37,930	63,970	77,090	88,770	100,030	111,190

# SUMMARY OF TBM SAFETY ANALYSIS

PLAN 1 .....									
DATE OF PPE	MAXIMUM RESERVATION CAPACITY	ELEVATION STORAGE		INITIAL VALUE		SPILLWAY CHERT		TOP OF DAM	
		OUTLINE		792.00		792.00		795.67	
		0.00		0.00		224.00		330.00	
		0.00		0.00		0.00		867.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00		0.00		0.00	
		0.00		0.00					

END

DATE  
FILMED

11-81

DTIC